



**INDIAN INSTITUTE OF TECHNOLOGY BOMBAY**  
**ESTATE OFFICE**  
**NOTICE INVITING TENDER**

Telephone No. 022 2576/4995,022/2159/6922 email id [drestate@iitb.ac.in](mailto:drestate@iitb.ac.in)

IIT Bombay invites signed Technical Bid & Financial Bid for the following work from the contractors having similar experience in Central Government Departments / State Government Departments / Central or State Autonomous Bodies / Central or State Public Sector Undertakings / in reputed Private Companies. The detail of work is given below:

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD (Rs.)	Mode of Tender	Duration of contract
1	Development of parking in between NN Main Building & Main Road located Westside of Main Building Annex. <b>EO/A/INFRA/WKS-201/25-26</b>	<b>Rs.1,78,51,691/-</b>	<b>Rs.3,57,000/-</b>	<b>Item rate offline mode</b>	<b>06 MONTHS</b>

**Intending bidders need to register themselves on the IIT Bombay portal i.e. <https://portal.iitb.ac.in/vrp/index.jsp> to get User ID and Password. Please visit [https://portal.iitb.ac.in/vrp/vrp\\_srm\\_docs.jsp](https://portal.iitb.ac.in/vrp/vrp_srm_docs.jsp) for configuration process and user manual. For queries regarding vendor registration, and configuration process please contact on 022 - 2159 3001 (MDM Help-desk).**

All tender documents, forms, etc are available online on <https://www.iitb.ac.in/resources/vendors-tenders> and Central Public Procurement Portal (CPPP) e-tender publishing portal of the Government of India.

Date of submission of technical and financial bids, in 2 separate envelopes is on 21.01.2026 from 09:15 a.m to 11:15 a.m. in the tender box at 1st floor, Conference room, Estate Office. **The date of opening the technical Bid will be 21.01.2026 at 11:30 a.m and the date of opening of financial bid is on 28.01.2026 (Tentative)**

Interested contractors/agencies are requested to submit Technical bid and Financial bid in the Tender Box of the Estate Office. All contractors/agencies should submit technical bid with the following documents, failing to which their tender will be summarily rejected from the tendering process:

1) **i.** Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited :

Three similar completed works costing not less than the amount equal to **40%** of estimated cost put to tender,

OR

Two similar completed works, costing not less than the amount equal to **50%** of the estimated cost put to tender

Or

One similar completed work of aggregate cost not less than the amount equal to **80%** of the estimated cost.

**ii.** One completed work of any nature (either part of (i) or a separate one) costing not less than the amount equal to **40%** of the estimated cost put to tender with some Central Government Departments / State Government Departments / State or Central Autonomous Bodies / State or Central Public Sector undertakings.

2) Submit a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp, otherwise tender will be rejected.

3) P. F. registration certificate.

4) P. F. challans of last 12months.

5) (i) ESIC registration certificate and copies of ESIC challans of last 12months. OR (ii) Contractors' all risks insurance (CAR policy) / Mediclaim policy.

6) PAN card.

7) GST registration certificate.

8) Income Tax Return for last 03 years i.e. of **2022-23, 2023-24 and 2024-25.**

9) List of Equipment's, Machinery, Tools.

10) List of Technical Staff with copies of their Degree/diploma certificate.

11) Submit DD/FDR/BG of Rs. 3,57,000/- in the name of "The Registrar, IIT Bombay" in the Technical Bid Envelope.

12) Power of Attorney, if any.

13) Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.

14) **Litigation history** of the agency is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.

15) Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.

16) Detail statement for work completed, work in hand including balance commitment of work should be enclosed for last three year commencing from 1st April and ended with 31st March and contractor should submit his details as per **Annexure'A'** format with support of xerox copies of work order and work completion certificates, otherwise the bid capacity will not be calculated and his technical bid will be summarily rejected.

17) **Labour Licence** obtained in the past 03 years

18) Index Sheet

#### **Terms & Conditions :**

**Those contractors who do not have documents mentioned above from Sr. No. 1 to 18 need not apply as it is mandatory documents to qualify in technical bids.**

The selected bidder should submit a **Performance Guarantee for 5%** of the quoted amount. The time allowed for submission of the Performance Guarantee from the date of issue of the letter of acceptance is 14 days.

The work will be executed with lowest bidder as per the terms and conditions of work order and tender documents signed by the lowest bidder.

The validity of the bids will be valid for 6 months from the date of opening of tender.

No work will be subletted to third party. If found payment of final bill will not be processed and the contractor's name will removed from the enlistment without giving him further notice.

The rates is prepared from CPWD DSR 2023 rates & rate analysis.

Contractors are strictly prohibited from engaging in any correspondence related to tender documents with anyone other than the Tender Section. Any violation will result in disqualification from all future tenders.

IIT Bombay reserve its rights to reject any or all tenders without assigning any reason and without any reference.IIT Bombay reserves the right to request a detailed justification of the quoted rates from the lowest bidder, if deemed necessary by the Engineer-in-Charge. Should the justification provided by the bidder be considered unsatisfactory or unsubstantiated, the Engineer-in-Charge shall have full authority to reject the bid, irrespective of it being the lowest.

**sd/-**  
**Superintending Engineer (I/C)**

**TO BE UPLOADED ON SRM TENDERING PORTAL WITH FINANCIAL BID**

**ANNEXURE 'A' (FORMAT)  
TECHNICAL BID**

File No. : EO/A/INFRA/WKS-201/25-26

Name of Work : Development of parking in between NN Main Building & Main Road located Westside of Main Building Annex.

Name of the Contractor -----

Sr. No.	Name of Client	Name of Works	2022-23 (In Lakhs)	2023-2024 (In Lakhs)	2024-2025 (In Lakhs)	2025-2026 (In Lakhs)	
						Completed	Balance
			-	-	-	-	-
			-	-	-	-	-
Total Amount (In Lakhs)			-	-	-	-	-

Note : Contractor must submit his details as per Annexure 'A' with declaration stating that **he is possessing all the original copies of work orders and experience certificates, it will be produced as and when required to IIT Bombay.** However, if it is found false at later stage, the contractor will be debarred or blacklisted. Whereas, if information is not submitted as per Annexure 'A' format his bid capacity will not be calculated and his tender will be summarily rejected.

6  
22/12  
Superintending Engineer (I/C)  
14/12  
16/12  
17/12

Signature of Contractor  
Name & Address in full

## WORKS UNDERTAKING

EO/A/INFRA/WKS-201/25-26

To,  
Superintending Engineer (I/C)  
Indian Institute of Technology,  
Powai, Mumbai – 400 076.

Sub : Development of parking in between NN Main Building & Main Road located Westside of Main Building Annex.

Dear Sir,

We are hereby quoting all the rates for the attached schedule of short tender of the above mentioned job.

We hereby accept & signed all the General Terms and Conditions and special Conditions of Contract.

The work will be completed within specified time limit of 06 months as mentioned in the notice inviting for short tenders.

The following information is required to be provided.

I / We agree to keep the tender open for One Hundred and Eighty (180) days from the due date of its opening / One Hundred and Eighty days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system and not to make any modification in its terms and conditions.

	Male	Female
No. of Unskilled casual labour to be required per day.		
No. of Skilled casual labour to be required per day.		
Total Mandays required for completion of work.		

Thanking you,

Yours faithfully,

Signature of the Contractor  
With official Seal / Stamp of the firm

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY  
ESTATE OFFICE

Name of work: Development of parking in between NN Main Building & Main Road located Westside of Main Building Annex.

Sr. No.	Schedule/Description of work	Qty	Unit	Rate in Rs.	Amount in Rs.
1	Dismantling plain cement concrete work including breaking concrete by chiselling, wedging etc., and stacking the debris upto a distance of 50 metres or spreading as directed.	5.00	m3	Rs...../- Rate in words _____ _____ )	
2	Removing soling without dust nuisance including sorting out the stone chips and debris separately and stacking upto distance of 50 metres as directed.	5.00	m3	Rs...../- Rate in words _____ _____ )	
3	Pulling down stone masonry in cement mortar with plaster / pointing without dust nuisance including sorting out the stone chips and debris separately and stacking upto distance of 50 metres or spreading the debris as directed.	2.00	m3	Rs...../- Rate in words _____ _____ )	
4	Dismantling burnt brick masonry (in cement mortar) with plaster including sorting out serviceable bricks and lowering down debris, stacking the same and debris separately upto a distance of 50 meters as directed etc. complete..	1.00	m3	Rs...../- Rate in words _____ _____ )	
5	Dismantling Reinforced cement concrete work including breaking concrete by chiselling, wedging including scaffolding, covering area with jute kantan to avoid spreading of dust etc., lowering down the debris from nay height and stacking the same upto a distance of 50 metres as directed.	2.00	m3	Rs...../- Rate in words _____ _____ )	
6	Excavation for foundation, trenches, Roadway etc. in earth, soil of all types, sand, gravel, soft and hard murum, soft rock etc. including removing the excavated materials up to a distance of 50 meters beyond the site of work and lift up to 1.50 meters, stacking and spreading as directed preparing the bed for the foundation and necessary dewatering using pump, backfilling, ramming, watering, including shoring and strutting, providing necessary barricading around excavated area etc. complete.	156.00	m3	Rs...../- Rate in words _____ _____ )	
7	Disposing debris, loose stones, boulders, concrete pieces broken etc. collected and stacked as directed including loading in trucks, transporting out of IIT Campus including obtaining approval from Government/ private land owners for disposing off on to their approved location. The contractor will be solely responsible for disposing debris out of campus and the debris are to be removed from site within 72 hours from stacking (30% voids will be deducted from actual measurement for debris, loose stones, boulders, concrete pieces).	35.00	m3	Rs...../- Rate in words _____ _____ )	
8	Laying dry trap / rubble stone soling of required thickness including hand packing and compacting etc. complete using IITB stone including trasporting stone from various locations from IIT campus to working site and cutting stones/ bouldres in piceses by mechanical or manual means as per requirement etc.including including transportation of stones upto a distance of 50 m etc.complete as directed.(Payment of cutting of stone and transportation beyond a distance of 50 m will be paid in respective items)	24.00	m3	Rs...../- Rate in words _____ _____ )	
9	Providing uncoursed rubble masonry upto plinth level (using IITB stones)of trap stones in cement mortar 1:6 (Cement:sand/grit) including racking out joints when plastering is to be done, striking out joints, watering , including providing header stones @ 1 header per sqm. to the full thickness of wall, providing weep holes, with 100mm dia pvc pipes including collecting and transporting stone stacked in IITB Campus upto working site, cutting stones/ bouldres in piceses by mechanical or manual means as per requirement etc. including transportation of stones upto a distance of 50 m etc.complete as directed.(Payment of PVC pipe,cutting of stone and transportation beyond a distance of 50 m will be paid in respective items)	42.00	m3	Rs...../- Rate in words _____ _____ )	
10	Providing and laying dry trap / rubble stone(using IITB stones) for pitching to the sloping side in average 200 to 300mm thickness laid in courses and required profile with hammer dressed stones having no side less than 150mm, with minimum depth of 200mm, cutting, dressing and levelling the undulation of sloping surface, preparing the bed etc including transportation of stones upto a distance of 50 m etc.complete as directed.(Payment of cutting of stone and transportation beyond a distance of 50 m will be paid in respective items)	300.00	m2	Rs...../- Rate in words _____ _____ )	

11	Cutting stones/ bouldres in piceses by mechanical or manual means as per requirement etc. complete as directed.	141.00	m3	Rs...../- Rate in words _____ _____ )
12	Transporting dry trap / rubble stone various locations of IITB Campus upto working site.(20% voids will be deducted from actual measurement of truck).	141.00	m3	Rs...../- Rate in words _____ _____ )
13	Providing and laying cement concrete 1:11/2: 3 (M-20) plinth level to upto any floor using sand as fine aggregate and graded stone aggregate 20mm maximum size for foundation, coping and bedding, levelling, dewatering by any means, compaction, finishing, curing etc. complete all as directed.	16.00	m3	Rs...../- Rate in words _____ _____ )
14	Providing and casting in position ready mixed or machine batched M-20 grade cement concrete (Min cement content 270Kg/Cum) for foundation, coping and bedding etc. as per approved excluding shuttering, including compaction, finishing, curing etc. including cost of admixtures in recommended proportions as per relevant IS code to accelerate/ retard setting of concrete,improve workability without impairing strength and durability as per direction of the Engineer-in-charge including casting cubes and testing.	12.00	m3	Rs...../- Rate in words _____ _____ )
15	Construction of granular sub-base, Grade-V having gradation as per MORTH table 400-1 (size range 75 mm to 0.425 mm) by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material using machinery to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge, collecting samples, testing as per section 900 of MORTH and submitting reports etc. completed as directed. (Note : The mix design with all relevant data to be submitted & prior approval is to be obtained from IIT Bombay. Compacted thickness will be taken for payment.)	1056.00	m3	Rs...../- Rate in words _____ _____ )
16	Construction of dry lean cement concrete over compacted granular sub base (GSB) with coarse and fine aggregate conforming to as per relevant IS code, the size of coarse aggregate not exceeding 26.5 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per MORTH, Table 600-1, cement content not to be less than 150 Kg/cum of concrete, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer-in- charge including collecting samples, testing and submitting reports etc. completed as directed. Specification, mix design, methodology and testing should be done as per IRC 15: 2017. (Note : The mix design with all relevant data to be submitted & prior approval is to be obtained from IIT Bombay. Compacted thickness will be taken for payment.)	704.00	m3	Rs...../- Rate in words _____ _____ )
17	Providing and laying in position Ready mix or machine batched M-30 grade cement concrete (with minimum cement content 350Kg/Cum)for all work up to plinth level for reinforced cement concrete work, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per relevant IS code to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge including compacting, roughening the surface if special finish is to be provided, casting cubes and testing etc. completed as directed.	33.00	m3	Rs...../- Rate in words _____ _____ )
18	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Foundations, footings, bases of columns, coping, raft etc.	117.00	m2	Rs...../- Rate in words _____ _____ )
19	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	115.00	m2	Rs...../- Rate in words _____ _____ )
20	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Suspended floors, roofs, landings, staircase waste slab, balconies, cantilever chajjas and access platform	5.00	m2	Rs...../- Rate in words _____ _____ )

21	Providing and fixing in position for steel bar having grade Fe-500D or more for reinforcement of various diameters for R.C.C. footings, foundations, slabs, beams, columns, canopies, staircases, chajjas, lintels, padies, coping, fins, dowel bars with sleeve, tie bar, any other required work etc. as per detailed designs, drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed as directed.	1952.00	Kg	Rs...../- Rate in words _____ _____)
22	Providing and fabricating structural steel works in rolled sections like joists, channels, angles, tees, hollow sections and any other required sections etc. as per detailed designs & drawings for supports, rafters, purlins, railing, staircase and any other work including fixing in position with connecting plates, braces and welding, riveting, bolting as necessary including one coat of redoxide priming coat complete.	100.00	Kg	Rs...../- Rate in words _____ _____)
23	Providing second class burnt brick masonry with IS approved quality well burnt bricks having in cement mortar 1:6 in superstructure including striking joints, racking out joints, watering and scaffolding complete.	21.00	m3	Rs...../- Rate in words _____ _____)
24	Providing internal cement plaster 20mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces in all positions including curing etc. completed as directed.	151.00	m2	Rs...../- Rate in words _____ _____)
25	Raising manhole cover and frame of any size slab to required level including dismantling existing slab and making good the damage as required (a) Rectangular manhole/ chamber of any size	2.00	Nos	Rs...../- Rate in words _____ _____)
26	Raising manhole cover and frame of any size slab to required level including dismantling existing slab and making good the damage as required (b) Circular manhole of any size	2.00	Nos	Rs...../- Rate in words _____ _____)
27	Providing and fixing 150mm(ID)dia ISI approved HDPE pipes manufactured by ARHAM Engineering/ BERLIA /NOCIL / PIL with wall thickness of 6 mm to 8mm for taking sewage waste water with all required fittings such as bend, elbows etc. with proper line and gradient connecting all joints with fusion butt welding by using suitable welding machine or hot plate, testing the line & joint as per manufacturer specification etc. all complete as directed by Engineer In-charge.	10.00	Rmt	Rs...../- Rate in words _____ _____)
28	Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface in white/ yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc complete. (Two or more coats)	482.00	m2	Rs...../- Rate in words _____ _____)
29	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	16.00	m3	Rs...../- Rate in words _____ _____)
30	Providing and laying Lacquer finish coloured paver blocks in specified pattern 80mm thick for floor and steps etc. with compressive strength not less than 45 N/sqmm over and including 50mm thick compacted bed of fine sand in specified decorative designs with blocks of different colour and pattern including filling the joints with fine sand and cleaning completed as directed.	5278.00	m2	Rs...../- Rate in words _____ _____)



31	Laying old cement concrete interlocking paver blocks of any design/shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. including transporting old paver blocks from anywhere inside IITB campus all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	1759.00	m2	Rs...../- Rate in words _____ _____)	
32	Providing lowering, and laying 300mm dia NP2 class R.C.C. spun pipes conforming to IS 458 of 300 mm dia (n.b) with necessary collars, laid to correct grade, alignment and levels at all depth including cutting to required length, jointing with hemp yarn and cement mortar 1:2 caulking the joints, finishing, curing etc. complete as directed.	30.00	Rmt	Rs...../- Rate in words _____ _____)	
33	Providing and fixing precast RCC slab for drain cover and chamber cover of required size with M-25 grade concrete and reinforced with 10mm dia main steel bars (along shorter span) and 8mm. dia distribution bars (along longer span) at 100mm center to center including making steel form work, making temporary concrete platform for casting, compaction using surface vibrator, with two lifting hooks of 6mm dia / holes of 25mm dia finishing the surface with smooth cement finish curing, placing the precast slab in proper position etc. complete as directed.	0.50	m3	Rs...../- Rate in words _____ _____)	
34	Providing and applying one coat of acrylic primer and two coats of exterior acrylic paint of approved colour & shade of IITB approved manufacturer i.e. Berger, Asian, Killick Nixon, Goodlass, Nerolac, ICI, Decocem and as per manufacturer's specification on old or new plastered surface over concrete / brickwork, stonework as per manufacturer's specification including scaffolding and cleaning the surface thoroughly with coir brush, watering the surface etc. complete including covering the floor, window glass with plastic sheet etc. all complete as directed by Engineer In-charge.	111.00	m2	Rs...../- Rate in words _____ _____)	
35	Providing Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing in proper line and level, preparing the joints for receiving the pointing all complete as directed.	393.00	m2	Rs...../- Rate in words _____ _____)	
36	Providing and fixing 600mm x 600mm rectangular Heavy duty RCC grating covers with frame for inspection chamber / manhole / gully trap/ over storm water drain and other required places manufactured by M/s.KK or IITB approved make including closing the gaps between frame and surface with cement mortar all complete as directed.	55.00	Each	Rs...../- Rate in words _____ _____)	
37	Painting roadside kerbing in black and yellow colour alternatively road marking paint of approved colour, shade and manufacturer including cleaning the surface thoroughly etc. complete	52.00	m2	Rs...../- Rate in words _____ _____)	
38	Providing and applying one priming coat of IITB approved brand over steel and other metal surface, including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering etc.	10.00	m2	Rs...../- Rate in words _____ _____)	
39	Providing and applying two coats of synthetic enamel paint of IITB approved brand and shade to wood and steel work Scrapping, cleaning, covering the floor, windows, instruments during painting etc. complete.	10.00	m2	Rs...../- Rate in words _____ _____)	
40	Hire charges for providing J.C.B for cutting and leveling the heaps of soil, for desilting / widening/deepening the kachha nallah /drains including necessary labour, operator, fuel etc. excavating, shifting, spreading and leveling the soil / debris at low lying area using the machinery etc. all complete as directed.	8.00	Per Hr.	Rs...../- Rate in words _____ _____)	

41	Consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres.	7037.00	m2	Rs...../- Rate in words _____ _____ )
42	Providing and fixing 100 mm dia. PVC Pipes for weep hole in the UCR wall including cutting as directed.	59.00	Rmt	Rs...../- Rate in words _____ _____ )
				Total Amount
				CGST@9%
				SGST@9%
				Net Amount
				Say Rs.

Amount in Rs. \_\_\_\_\_ )

(Rates for all items & net amount of total to be filled with figure and words. If it is not done, it will be assumed as incomplete tender & tender opening committee will reject your offer at the time of opening of tenders/quotations).

**1) Note : Contractors are requested to quote their own rates against each item in financial bid.**

2) If you will engage labourer 20 or more any day, you have to get labour licence as per contract Regulation & Abolition Act 1970 Rule 1971, and also, you have to keep all such record for inspection to the Principal Employer. If you will engage labour up to 10 Nos. per day, you have to file returns after completion of work as per Building & Construction Act to the Office of Regional Labour Commissioner (Central), Sion, Mumbai.

3) This work is to be executed as per the clauses mentioned in the tender document signed by you.

4) Taxes as per government notification time to time.

**5) Contractor must pay GST Taxes to concern authority within 30 days time limit after receipt of payment from IIT Bombay & said record must be submitted to IIT Bombay Accounts Section, otherwise action will be taken as deemed fit.**

6) If any malpractices / fraud / negligent professional behaviour or any discrepancy / inconsistency / disparity / deviation / disagreement / dissimilarity / mismatch noticed, their contract will be terminated by issuing one month notice by following legal procedure and will be blacklisted and informed to all Government Authorities and Organisations.

7) Tender will be rejected if white ink applied for correction in the schedule of work.

8) In the case of Item rate tenders, only rates quoted shall be considered. Any tender containing percentage below / above the rates quoted is liable to be rejected. Rates quoted by the contractor in item rate tender in figures and words shall be accurately filled in so that there is no discrepancy in the rates written in figures and words. However, if a discrepancy is found, the rates which correspond with the amount worked out by the contractor shall unless otherwise proved be taken as correct. If the amount of an item is not worked out by the contractor or it does not correspond with the rates written either in figures or in words, then the rates quoted by the contractor in words shall be taken as correct. Where the rates quoted by the contractor in figure and in words tally, but the amount is not worked out correctly, the rates quoted by the contractor will unless otherwise proved be taken as correct and not the amount. In event no rate has been quoted for any item(s), leaving space both in figure(s), words(s), and amount blank, it will be presumed that the contractor has included the cost of this / these item(s) in other items and rate for such item(s) will be considered as zero and work will be required to be executed accordingly.

sd/-  
Superintending Engineer (I/C)

Signature and official Stamp of Contractor

## INDEX SHEET

Sr. No.	Content	Page No. From - To
1	Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited : Three similar completed works costing not less than the amount equal to 40% of estimated cost put to tender, OR Two similar completed works, costing not less than the amount equal to 50% of the estimated cost put to tender Or One similar completed work of aggregate cost not less than the amount equal to 80% of the estimated cost.	
2	Annexure 'A'	
3	Submit a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp.	
4	Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.	
5	P. F. registration certificate.	
6	P. F. challans of last 12months.	
7	ESIC registration certificate and copies of ESIC challans of last 12months. OR Contractors' all risks insurance (CAR policy) / Mediclaim policy.	
8	PAN card.	
9	GST Registration certificate	
10	Income Tax Return for last 03 years i.e. of 2022-23, 2023-24 & 2024-25.	
11	List of Equipment's, Machinery, Tools.	
12	List of Technical Staff with copies of their Degree/diploma certificate.	
13	Earnest Money Deposit	
14	Power of Attorney, if any.	
15	Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.	
16	Litigation history of the agency is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.	
17	Labour Licence obtained during last 03 years	

**Signature & stamp of the Contractor**