



INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
ESTATE OFFICE
NOTICE INVITING TENDER

Telephone No. 022 2576/4995,022/2159/6922 email id drestate@iitb.ac.in

IIT Bombay invites signed Technical Bid & Financial Bid for the following work from the contractors having similar experience in Central Government Departments / State Government Departments / Central or State Autonomous Bodies / Central or State Public Sector Undertakings / in reputed Private Companies. The detail of work is given below:

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD (Rs.)	Mode of Tender	Duration of contract
1	Construction of approach road from Main road to EHV plot along with Utilities at Paspoli area EO/A/WORKSHOP/WKS-204/25-26	Rs.3,32,64,633/- including 18% GST.	Rs. 6,65,000/-	Item rate offline mode	06 MONTHS

Intending bidders need to register themselves on the IIT Bombay portal i.e. <https://portal.iitb.ac.in/vrp/index.jsp> to get User ID and Password. Please visit https://portal.iitb.ac.in/vrp/vrp_srm_docs.jsp for configuration process and user manual. For queries regarding vendor registration, and configuration process please contact on 022 - 2159 3001 (MDM Help-desk).

All tender documents, forms, etc are available online on <https://www.iitb.ac.in/resources/vendors-tenders> and Central Public Procurement Portal (CPPP) e-tender publishing portal of the Government of India.

Date of submission of technical and financial bids, in 2 separate envelopes is on 21.01.2026 from 09:15 a.m to 11:15 a.m. in the tender box at 1st floor, Conference room, Estate Office. **The date of opening the technical Bid will be 21.01.2026 at 11:30 a.m and the date of opening of financial bid is on 28.01.2026 (Tentative)**

Interested contractors/agencies are requested to submit Technical bid and Financial bid in the Tender Box of the Estate Office. All contractors/agencies should submit technical bid with the following documents, failing to which their tender will be summarily rejected from the tendering process:

1) **i.** Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited :

Three similar completed works costing not less than the amount equal to **40%** of estimated cost put to tender,

OR

Two similar completed works, costing not less than the amount equal to **50%** of the estimated cost put to tender

Or

One similar completed work of aggregate cost not less than the amount equal to **80%** of the estimated cost.

ii. One completed work of any nature (either part of (i) or a separate one) costing not less than the amount equal to **40%** of the estimated cost put to tender with some Central Government Departments / State Government Departments / State or Central Autonomous Bodies / State or Central Public Sector undertakings.

2) Submit a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp, otherwise tender will be rejected.

3) P. F. registration certificate.

- 5) (i) ESIC registration certificate and copies of ESIC challans of last 12 months. OR (ii) Contractors' all risks insurance (CAR policy) / Mediclaim policy.
- 6) PAN card.
- 7) GST registration certificate.
- 8) Income Tax Return for last 03 years i.e. of **2022-23, 2023-24 and 2024-25**.
- 9) List of Equipment's, Machinery, Tools.
- 10) List of Technical Staff with copies of their Degree/diploma certificate.
- 11) Submit DD/FDR/BG of Rs. 6,65,000/- in the name of "The Registrar, IIT Bombay" in the Technical Bid Envelope.
- 12) Power of Attorney, if any.
- 13) Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.
- 14) **Litigation history** of the agency is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.
- 15) Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.
- 16) Detail statement for work completed, work in hand including balance commitment of work should be enclosed for last three year commencing from 1st April and ended with 31st March and contractor should submit his details as per **Annexure'A'** format with support of xerox copies of work order and work completion certificates, otherwise the bid capacity will not be calculated and his technical bid will be summarily rejected.
- 17) **Labour Licence** obtained in the past 03 years
- 18) Index Sheet

Terms & Conditions :

Those contractors who do not have documents mentioned above from Sr. No. 1 to 18 need not apply as it is mandatory documents to qualify in technical bids.

The selected bidder should submit a **Performance Guarantee for 5%** of the quoted amount. The time allowed for submission of the Performance Guarantee from the date of issue of the letter of acceptance is 14 days.

The work will be executed with lowest bidder as per the terms and conditions of work order and tender documents signed by the lowest bidder.

The validity of the bids will be valid for 6 months from the date of opening of tender.

No work will be subletted to third party. If found payment of final bill will not be processed and the contractor's name will be removed from the enlistment without giving him further notice.

The rates are prepared from CPWD DSR 2023 rates & rate analysis.

Contractors are strictly prohibited from engaging in any correspondence related to tender documents with anyone other than the Tender Section. Any violation will result in disqualification from all future tenders.

IIT Bombay reserve its rights to reject any or all tenders without assigning any reason and without any reference. IIT Bombay reserves the right to request a detailed justification of the quoted rates from the lowest bidder, if deemed necessary by the Engineer-in-Charge. Should the justification provided by the bidder be considered unsatisfactory or unsubstantiated, the Engineer-in-Charge shall have full authority to reject the bid, irrespective of it being the lowest.

sd/-
Superintending Engineer (I/C)

TO BE UPLOADED ON SRM TENDERING PORTAL WITH FINANCIAL BID

**ANNEXURE 'A' (FORMAT)
TECHNICAL BID**





File No. : EO/A/WORKSHOP/WKS-204/25-26

Name of Work : Construction of approach road from main road to EHV plot along with utilities at Paspoli area.

Name of the Contractor -----

Sr. No.	Name of Client	Name of Works	2022-23 (In Lakhs)	2023-2024 (In Lakhs)	2024-2025 (In Lakhs)	2025-2026 (In Lakhs)	
						Completed	Balance
			-	-	-	-	-
			-	-	-	-	-
Total Amount (In Lakhs)			-	-	-	-	-

Note : Contractor must submit his details as per Annexure 'A' with declaration stating that **he is possessing all the original copies of work orders and experience certificates, it will be produced as and when required to IIT Bombay.** However, if it is found false at later stage, the contractor will be debarred or blacklisted. Whereas, if information is not submitted as per Annexure 'A' format his bid capacity will not be calculated and his tender will be summarily rejected.


Superintending Engineer (I/C)




Signature of Contractor
Name & Address in full

WORKS UNDERTAKING

EO/A/WORKSHOP/WKS-204/25-26

To,
Superintending Engineer (I/C)
Indian Institute of Technology,
Powai, Mumbai – 400 076.

Sub : Construction of approach road from main road to EHV plot along with utilities at Paspoli area.

Dear Sir,

We are hereby quoting all the rates for the attached schedule of short tender of the above mentioned job.

We hereby accept & signed all the General Terms and Conditions and special Conditions of Contract.

The work will be completed within specified time limit of 06 months as mentioned in the notice inviting for short tenders.

The following information is required to be provided.

I / We agree to keep the tender open for One Hundred and Eighty (180) days from the due date of its opening / One Hundred and Eighty days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system and not to make any modification in its terms and conditions.

	Male	Female
No. of Unskilled casual labour to be required per day.		
No. of Skilled casual labour to be required per day.		
Total Mandays required for completion of work.		

Thanking you,

Yours faithfully,

Signature of the Contractor
With official Seal / Stamp of the firm

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
ESTATE OFFICE

EO/A/INFRA/WKS -204/25-26

Name of work: Construction of approach road from Main road to EHV plot along with Utilities at Paspoli area

Sr. No.	Description of work	Qty	Unit	Rate in Rs.	Amount in Rs.
1	Excavation for foundation, trenches, Roadway etc. in earth, soil of all types, sand, gravel, soft and hard murum, soft rock etc. including removing the excavated materials up to a distance of 50 meters beyond the site of work and lift up to 1.50 meters, stacking and spreading as directed preparing the bed for the foundation and necessary dewatering using pump, backfilling, ramming, watering, including shoring and strutting, providing necessary barricading around excavated area etc. complete.	2623.00	m3	Rs...../- Rate in words _____ _____)	
2	Disposing murum, soil etc. collected and stacked as directed including loading in trucks, transporting out of IIT Bombay Campus upto a lead of 30km including royalty & obtaining approval from Government/ private land owners for disposing off on to their approved location. The contractor will be solely responsible for disposing murum, soil etc out of campus from the site within 72 hours from stacking (30% voids will be deducted in case of truck measurement).	525.00	m3	Rs...../- Rate in words _____ _____)	
3	Removing excavated earth or debris including loading in trucks and conveying to approved dumping point in IITB campus unloading spreading etc. complete. 30% voids will be deducted in case of truck measurement.	787.00	m3	Rs...../- Rate in words _____ _____)	
4	Laying dry trap / rubble stone soling of required thickness including hand packing and compacting etc. complete using IITB stone including transporting stone from various locations from IIT campus to Paspoli area up to working site and cutting the stone in required size as per requirement.	188.00	m3	Rs...../- Rate in words _____ _____)	
5	Laying dry trap / rubble stone soling of required thickness including hand packing and compacting in proper level all complete as directed by Engineer-in-charge.	2.00	m3	Rs...../- Rate in words _____ _____)	
6	Providing and laying cement concrete 1:11/2: 3 (M-20) plinth level to upto any floor using sand as fine aggregate and graded stone aggregate 20mm maximum size for foundation, coping and bedding, levelling, dewatering by any means, compaction, finishing, curing etc. complete all as directed.	95.00	m3	Rs...../- Rate in words _____ _____)	
7	Providing and casting in position ready mixed or machine batched M-20 grade cement concrete (Min cement content 270Kg/Cum) for foundation, coping and bedding etc. as per approved excluding shuttering, including compaction, finishing, curing etc. including cost of admixtures in recommended proportions as per relevant IS code to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer-in-charge including casting cubes and testing.	2.00	m3	Rs...../- Rate in words _____ _____)	
8	Providing and laying design mix/ ready mix cement concrete of M-40 grade, in roads using cement content as per design mix, using coarse sand and graded stone aggregate of 26.5 mm nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve of 32mm dia. having length not less than 500mm @ 300mm c/c, providing tie bars of 10mm dia. having length not less than 600mm @ 400 c/c wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for Transverse/ contraction/ expansion, construction & longitudinal joints by groove cutting machine, providing and filling joints using cold Polysulfide joint fillers and sealants including casting cubes and beams for testing the samples for compressive and flexural strength and submitting reports etc. completed as per direction of Engineer-in-charge. Note:- Cement content should be not be less than 385 kg/cum. Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer. Specification, mix design, methodology and testing should be done as per IRC 15: 2017. (Note : The mix design with all relevant data to be submitted & prior approval is to be obtained from IIT Bombay. Items of cutting groove, joint fillers, sealants, providing dowel bars with sleeve/ tie bars to be paid separately in respective items).	324.00	m3	Rs...../- Rate in words _____ _____)	
9	Construction of granular sub-base, Grade-V having gradation as per MORTH table 400-1 (size range 75 mm to 0.425 mm) by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material using machinery to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge, collecting samples, testing as per section 900 of MORTH and submitting reports etc. completed as directed. (Note : The mix design with all relevant data to be submitted & prior approval is to be obtained from IIT Bombay. Compacted thickness will be taken for payment.)	331.00	m3	Rs...../- Rate in words _____ _____)	

10	Construction of dry lean cement concrete over compacted granular sub base (GSB) with coarse and fine aggregate conforming to as per relevant IS code, the size of coarse aggregate not exceeding 26.5 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per MORTH, Table 600-1, cement content not to be less than 150 Kg/cum of concrete, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, for all leads & lifts, laid with a mechanical paver, compacting with 8-10 tonne vibratory roller, finishing and curing etc. complete as per direction of Engineer-in-charge including collecting samples, testing and submitting reports etc. completed as directed. Specification, mix design, methodology and testing should be done as per IRC 15: 2017. (Note : The mix design with all relevant data to be submitted & prior approval is to be obtained from IIT Bombay. Compacted thickness will be taken for payment.)	109.00	m3	Rs...../- Rate in words _____ _____)
11	Providing and laying in position Ready mix or machine batched M-40 grade cement concrete (with minimum cement content 390Kg/Cum) for all work up to plinth level for reinforced cement concrete work, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per relevant IS code to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge including compacting, roughening the surface if special finish is to be provided, casting cubes and testing etc. completed as directed.	531.00	m3	Rs...../- Rate in words _____ _____)
12	Providing and laying in position Ready mix or machine batched M-30 grade cement concrete (with minimum cement content 350Kg/Cum) for all work up to plinth level for reinforced cement concrete work, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per relevant IS code to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge including compacting, roughening the surface if special finish is to be provided, casting cubes and testing etc. completed as directed.	325.00	m3	Rs...../- Rate in words _____ _____)
13	Providing and laying in position ready-mixed or machine batched or machine mixed design mix M-25 (1:1:2) grade cement concrete (with minimum cement content 330Kg/Cum) for all work up to plinth level for reinforced cement concrete work, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per relevant IS code to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge including compacting, roughening the surface if special finish is to be provided, casting cubes and testing etc. completed as directed.	5.00	m3	Rs...../- Rate in words _____ _____)
14	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Foundations, footings, bases of columns, coping, raft etc.	211.00	m2	Rs...../- Rate in words _____ _____)
15	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	1850.00	m2	Rs...../- Rate in words _____ _____)
16	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Suspended floors, roofs, landings, staircase waste slab, balconies, cantilever chajjas and access platform	403.00	m2	Rs...../- Rate in words _____ _____)
17	Providing uncoursed rubble masonry upto plinth level (using IITB stones) of trap stones in cement mortar 1:6 (Cement:sand/grit) including racking out joints when plastering is to be done, striking out joints, watering , including providing header stones @ 1 header per sqm. to the full thickness of wall, providing weep holes, with 100mm dia pvc pipes including collecting and transporting stone stacked in IITB Campus, cutting stones/ bouldres in piceses as per requirement, etc. complete as directed.(Payment of PVC pipe shall be paid seperately)	2.00	m3	Rs...../- Rate in words _____ _____)
18	Providing and fixing in position tor steel bar having grade Fe-500D or more for reinforcement of various diameters for R.C.C. footings, foundations, slabs, beams, columns, canopies, staircases, chajjas, lintels, pardies, coping, fins, dowel bars with sleeve, tie bar, any other required work etc. as per detailed designs, drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed as directed.	65642.00	Kg	Rs...../- Rate in words _____ _____)
19	Cutting Transverse/ contraction/ expansion, construction & longitudinal joints by groove cutting machine upto required depth including labour, trasportation, tools and plants etc. compld as directed.	2304.00	Rmt	Rs...../- Rate in words _____ _____)
20	Providing and filling the joint using foam baker rod as base with cold Polysulfide with labour, trasportation, tools and plants etc. completed as directed.	2304.00	Rmt	Rs...../- Rate in words _____ _____)

21	Providing and fabricating structural steel works in rolled sections like joists, channels, angles, tees, hollow sections and any other required sections etc. as per detailed designs & drawings for supports, rafters, purlins, railing, staircase and any other work including fixing in position with connecting plates, braces and welding, riveting, bolting as necessary including one coat of redoxide priming coat.	2000.00	kg	Rs...../- Rate in words _____ _____)
22	Providing second class burnt brick masonry with IS approved quality well burnt bricks having in cement mortar 1:6 in superstructure including striking joints, racking out joints, watering and scaffolding complete.	25.00	m3	Rs...../- Rate in words _____ _____)
23	Providing and fixing 110 mm dia. PVC Pipes for weep hole in the RCC Retaining wall including cutting as directed.	480.00	Rmt	Rs...../- Rate in words _____ _____)
24	Providing and fixing 900mm x 600mm rectangular Heavy duty Grating FRP manhole covers with frame for inspection chamber / manhole / gulley trap/ over storm water drain and other required places manufactured by M/s.KK or IITB approved makeetc. all complete as directed.	37.00	Each	Rs...../- Rate in words _____ _____)
25	Providing and fixing 900mm x 450mm rectangular Heavy duty Composite FRP manhole covers with frame for inspection chamber / manhole / gulley trap/ over storm water drain and other required places manufactured by M/s.KK or IITB approved makeetc. all complete as directed.	5.00	Each	Rs...../- Rate in words _____ _____)
26	Providing and fixing 600mm x 450mm rectangular Heavy duty Grating FRP manhole covers with frame for inspection chamber / manhole / gulley trap/ over storm water drain and other required places manufactured by M/s.KK or IITB approved makeetc. all complete as directed.	1.00	Each	Rs...../- Rate in words _____ _____)
27	Providing and applying two coats of synthetic enamel paint of IITB approved brand and shade to wood and steel work. Scrapping, cleaning, covering the floor, windows, instruments during painting etc. complete.	12.00	m2	Rs...../- Rate in words _____ _____)
28	Providing and applying one coat of acrylic primer and two coats of exterior acrylic paint of approved colour & shade of IITB approved manufacturer i.e. Berger, Asian, Killick Nixon, Goodlass, Nerolac, ICI, Decocem and as per manufacturer's specification on old or new plastered surface over concrete / brickwork, stonework as per manufacturer's specification including scaffolding and cleaning the surface thoroughly with coir brush, watering the surface etc. complete including covering the floor, window glass with plastic sheet etc. all complete as directed by Engineer In-charge.	672.00	m2	Rs...../- Rate in words _____ _____)
29	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	17.00	m3	Rs...../- Rate in words _____ _____)
30	Providing and fixing in position GI weldmesh of 3mm wire with opening size 10mm x 10mm over the weep hole before filling media in the size of 200mmx200mm complete as per specifications etc. all complete as per the architectural drawings, complete as directed by Engineer-in-charge.	38.00	m2	Rs...../- Rate in words _____ _____)
31	Providing internal cement plaster 20mm thick in a single coat in cement mortar 1:4 without neen finish to concrete or brick surfaces in all positions including curing etc. completed as directed.	221.00	m2	Rs...../- Rate in words _____ _____)
32	Providing and laying dry trap / rubble stone pitching to the sloping side in average 200 to 300mm thickness laid in courses and required profile with hammer dressed stones having no side less than 150mm, with minimum depth of 200mm, cutting, dressing and levelling the undulation of sloping surface, preparing the bed etc all complete as directed.	120.00	m2	Rs...../- Rate in words _____ _____)

33	Providing Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing in proper line and level, preparing the joints for receiving the pointing all complete as directed.	240.00	m2	Rs...../- Rate in words _____ _____)
34	Painting roadside kerbing in black and yellow colour alternatively road marking paint of approved colour,shade and manufacturer including cleaning the surface thoroughly etc.complete	58.00	m2	Rs...../- Rate in words _____ _____)
35	Providing and laying dry trap / rubble stone pitching (using ITTB stones)to the sloping side in average 200 to 300mm thickness laid in courses and required profile with hammer dressed stones having no side less than 150mm, with minimum depth of 200mm, cutting, dressing and levelling the undulation of sloping surface, preparing the bed & including transportation etc all complete as directed.	120.00	m2	Rs...../- Rate in words _____ _____)
36	Providing and applying 2.5 mm thick road marking strips (retroreflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable Specifications.	43.00	m2	Rs...../- Rate in words _____ _____)
37	Manufacturing, supplying and fixing retro reflective sign boards of Mandatory/ Regulatory sign boards of 900 mm diameter with support length of 3750 mm made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bilingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours).Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing, specification and direction of Engineer-in-charge.	3.00	Each	Rs...../- Rate in words _____ _____)
38	Manufacturing, supplying and fixing retro reflective sign boards of Cautionary /warning sign boards of equilateral triangular shape having each side of 900 mm with support length of 3650 mm made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bilingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours).Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing, specification and direction of Engineer-in-charge.	3.00	Each	Rs...../- Rate in words _____ _____)
39	Providing, laying, spreading and compacting graded stone aggregate having gradation as per MORTH Table 400-13 (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge including collecting samples, testing as per section 900 of MORTH and submitting reports etc. completed as directed. (Note : The mix design with all relevant data to be submitted & prior approval is to be obtained from IIT Bombay. Compacted thickness will be taken for payment.)	109.00	Cum	Rs...../- Rate in words _____ _____)
40	Cutting the existing bituminous pavement upto 60mm thick depth with milling machine with conveyor belt including cleaning of the milled surface bottom & sides with brushes etc. complete & stacking of the milled material with mechanical transport at a distance of 50 mtr from working site etc. completed as directed.	1094.00	m2	Rs...../- Rate in words _____ _____)
41	Providing and laying 25mm thick open graded premix carpet cum seal coat with average 10mm thick stone chips, stone dust and premixed with VG-30 grade bitumin as per the mix design including cleaning , preparing the road surface, diverting traffic flow, supplying all materials hitting bitumen and chips in a computerized approved hot mixing plant, bringing to site laying the premix carpet cum seal coat in proper line, level, thickness with proper camber, using paver machine compacting with vibratory roller Including providing traffic diversion board, bricading with ribbon all etc. complet as per the direction of engineer incharge.	1094.00	m2	Rs...../- Rate in words _____ _____)

42	Disposing debris, loose stones, boulders, concrete pieces broken etc. collected and stacked as directed including loading in trucks, transporting out of IIT Campus including obtaining approval from Government/ private land owners for disposing off on to their approved location. The contractor will be solely responsible for disposing debris out of campus and the debris are to be removed from site within 72 hours from stacking (30% voids will be deducted from actual measurement for debris, loose stones, boulders, concrete pieces).	55.00	m3	Rs...../- Rate in words.....)	
					Total Amount
					CGST@9%
					SGST @9%
					Net Amount
					Say Rs.

Amount in Rs. _____

(Rates for all items & net amount of total to be filled with figure and words. If it is not done, it will be assumed as incomplete tender & tender opening committee will reject your offer at the time of opening of tenders/quotations).

1) **Note : Contractors are requested to quote their own rates against each item in final**

2) If you will engage labourer 20 or more any day, you have to get labour licence as per contract Regulation & Abolition Act 1970 Rule 1971, and also, you have to keep all such record for inspection to the Principal Employer. If you will engage labour up to 10 Nos. per day, you have to file returns after completion of work as per Building & Construction Act to the Office of Regional Labour Commissioner (Central), Sion, Mumbai.

3) This work is to be executed as per the clauses mentioned in the tender document signed by you.

4) Taxes as per government notification time to time.

5) **Contractor must pay GST Taxes to concern authority within 30 days time limit after receipt of payment from IIT Bombay & said record must be submitted to IIT Bombay Accounts Section, otherwise action will be taken as deemed fit.**

6) If any malpractices / fraud / negligent professional behaviour or any discrepancy / inconsistency / disparity / deviation / disagreement / dissimilarity / mismatch noticed, their contract will be terminated by issuing one month notice by following legal procedure and will be blacklisted and informed to all Government Authorities and Organisations.

7) Tender will be rejected if white ink applied for correction in the schedule of work.

8) In the case of Item rate tenders, only rates quoted shall be considered. Any tender containing percentage below / above the rates quoted is liable to be rejected. Rates quoted by the contractor in item rate tender in figures and words shall be accurately filled in so that there is no discrepancy in the rates written in figures and words. However, if a discrepancy is found, the rates which correspond with the amount worked out by the contractor shall unless otherwise proved be taken as correct. If the amount of an item is not worked out by the contractor or it does not correspond with the rates written either in figures or in words, then the rates quoted by the contractor in words shall be taken as correct. Where the rates quoted by the contractor in figure and in words tally, but the amount is not worked out correctly, the rates quoted by the contractor will unless otherwise proved be taken as correct and not the amount. In event no rate has been quoted for any item(s), leaving space both in figure(s), words(s), and amount blank, it will be presumed that the contractor has included the cost of this / these item(s) in other items and rate for such item(s) will be considered as zero and work will be required to be executed accordingly.

sd/-
Superintending Engineer (I/C)

Signature and official Stamp of Contractor

INDEX SHEET

Sr. No.	Content	Page No. From - To
1	Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited : Three similar completed works costing not less than the amount equal to 40% of estimated cost put to tender, OR Two similar completed works, costing not less than the amount equal to 50% of the estimated cost put to tender Or One similar completed work of aggregate cost not less than the amount equal to 80% of the estimated cost.	
2	Annexure 'A'	
3	Submit a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp.	
4	Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.	
5	P. F. registration certificate.	
6	P. F. challans of last 12months.	
7	ESIC registration certificate and copies of ESIC challans of last 12months. OR Contractors' all risks insurance (CAR policy) / Mediclaim policy.	
8	PAN card.	
9	GST Registration certificate	
10	Income Tax Return for last 03 years i.e. of 2022-23, 2023-24 & 2024-25.	
11	List of Equipment's, Machinery, Tools.	
12	List of Technical Staff with copies of their Degree/diploma certificate.	
13	Earnest Money Deposit	
14	Power of Attorney, if any.	
15	Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.	
16	Litigation history of the agency is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.	
17	Labour Licence obtained during last 03 years	

Signature & stamp of the Contractor